

| 6国補第66-116号舗装復旧工事 | | | | | | | | | | | | | | 単独 | | | |
|--------------------|-----|------------|------|----------------|------|--------|------|---------|---|---------|---|--------|---|--------|------|----------------|----------------|
| 舗装切断工 | | | | | | | | | | | | | | | | | |
| ①白山 | ②白山 | ③白山 | ④中原町 | ⑤中原町 | ⑥294 | ⑦294 | ⑧井野台 | | | 合計 | | | | | | | |
| 2.90 | + | 10.60 | + | 0.00 | + | 3.60 | + | 7.75 | + | 16.20 | + | 5.20 | + | 10.00 | = | 56.25 | m |
| 設計値 | | | | | | | | | | | | | | = | 56 | m | |
| 舗装版掘削積込(As) | | | | | | | | | | | | | | | | | |
| ①白山 | ②白山 | ③白山 | ④中原町 | ⑤中原町 | ⑥294 | ⑦294 | ⑧井野台 | | | 合計 | | | | | | | |
| 176.954 | + | 422.671 | + | 161.900 | + | 72.181 | + | 315.412 | + | 407.333 | + | 62.768 | + | 15.120 | = | 1634.339 | m ² |
| 設計値 | | | | | | | | | | | | | | = | 1630 | m ² | |
| 不陸整正3.1未満(補足有) | | 路盤工事道 | | 幅員狭いため振動ローラー使用 | | | | | | | | | | | | | |
| ①白山 | ②白山 | ③白山 | ④中原町 | ⑤中原町 | ⑥294 | ⑦294 | ⑧井野台 | | | 合計 | | | | | | | |
| 0.000 | + | 15.883 | + | 129.660 | + | 0.000 | + | 66.535 | + | 36.939 | + | 0.000 | + | 0.000 | = | 249.017 | m ² |
| 設計値 | | | | | | | | | | | | | | = | 249 | m ² | |
| 不陸整正3.1以上(補足有) | | | | | | | | | | | | | | | | | |
| ①白山 | ②白山 | ③白山 | ④中原町 | ⑤中原町 | ⑥294 | ⑦294 | ⑧井野台 | | | 合計 | | | | | | | |
| 176.954 | + | 406.788 | + | 32.240 | + | 72.181 | + | 248.877 | + | 370.394 | + | 62.768 | + | 15.120 | = | 1385.322 | m ² |
| 設計値 | | | | | | | | | | | | | | = | 1380 | m ² | |
| 上層路盤工 | | | | | | | | | | | | | | | | | |
| ①白山 | ②白山 | ③白山 | ④中原町 | ⑤中原町 | ⑥294 | ⑦294 | ⑧井野台 | | | 合計 | | | | | | | |
| 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | = | 0.000 | m ² |
| 設計値 | | | | | | | | | | | | | | = | 0 | m ² | |
| 舗装版切削 | | | | | | | | | | | | | | | | | |
| ①白山 | ②白山 | ③白山 | ④中原町 | ⑤中原町 | ⑥294 | ⑦294 | ⑧井野台 | | | 合計 | | | | | | | |
| 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | = | 0.000 | m ² |
| 設計値 | | | | | | | | | | | | | | = | 0 | m ² | |
| 舗装工(再密As) | | 車道3.0超 | | | | | | | | | | | | | | | |
| ①白山 | ②白山 | ③白山 | ④中原町 | ⑤中原町 | ⑥294 | ⑦294 | ⑧井野台 | | | 合計 | | | | | | | |
| 176.954 | + | 422.671 | + | 82.940 | + | 72.181 | + | 300.072 | + | 370.394 | + | 62.768 | + | 15.120 | = | 1503.100 | m ² |
| 設計値 | | | | | | | | | | | | | | = | 1500 | m ² | |
| 舗装工(再密As) | | 車道1.4～3.0 | | | | | | | | | | | | | | | |
| ①白山 | ②白山 | ③白山 | ④中原町 | ⑤中原町 | ⑥294 | ⑦294 | ⑧井野台 | | | 合計 | | | | | | | |
| 0.000 | + | 0.000 | + | 78.960 | + | 0.000 | + | 15.340 | + | 36.939 | + | 0.000 | + | 0.000 | = | 131.239 | m ² |
| 設計値 | | | | | | | | | | | | | | = | 131 | m ² | |
| 舗装工(細粒As) | | 歩道1.4未満 | | | | | | | | | | | | | | | |
| ①白山 | ②白山 | ③白山 | ④中原町 | ⑤中原町 | ⑥294 | ⑦294 | ⑧井野台 | | | 合計 | | | | | | | |
| 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | = | 0.000 | m ² |
| 設計値 | | | | | | | | | | | | | | = | 0 | m ² | |
| 殻運搬処理(As t ≤ 15cm) | | | | | | | | | | | | | | | | | |
| ①白山 | ②白山 | ③白山 | ④中原町 | ⑤中原町 | ⑥294 | ⑦294 | ⑧井野台 | | | 合計 | | | | | | | |
| 8.848 | + | 21.134 | + | 8.095 | + | 3.609 | + | 15.771 | + | 20.367 | + | 3.138 | + | 0.756 | = | 81.72 | m ³ |
| 設計値 | | | | | | | | | | | | | | = | 81 | m ³ | |
| 区画線設置(実線15cm) | | 消火栓、外側線 | | | | | | | | | | | | | | | |
| ①白山 | ②白山 | ③白山 | ④中原町 | ⑤中原町 | ⑥294 | ⑦294 | ⑧井野台 | | | 合計 | | | | | | | |
| 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | + | 47.000 | + | 0.000 | + | 0.000 | + | 0.000 | = | 47.0 | m |
| 設計値 | | | | | | | | | | | | | | = | 47 | m | |
| 区画線設置(矢印・記号・文字) | | ダイヤ・止まれ | | | | | | | | | | | | | | | |
| ①白山 | ②白山 | ③白山 | ④中原町 | ⑤中原町 | ⑥294 | ⑦294 | ⑧井野台 | | | 合計 | | | | | | | |
| 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | + | 13.400 | + | 13.400 | + | 0.000 | + | 0.000 | = | 26.8 | m |
| 設計値 | | | | | | | | | | | | | | = | 26 | m | |
| 区画線設置(実線45cm) | | 横断歩道 + 停止線 | | | | | | | | | | | | | | | |
| ①白山 | ②白山 | ③白山 | ④中原町 | ⑤中原町 | ⑥294 | ⑦294 | ⑧井野台 | | | 合計 | | | | | | | |
| 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | + | 2.000 | + | 1.600 | + | 0.000 | + | 0.000 | = | 3.6 | m |
| 設計値 | | | | | | | | | | | | | | = | 3 | m | |
| 区画線設置(破線30cm) | | | | | | | | | | | | | | | | | |
| ①白山 | ②白山 | ③白山 | ④中原町 | ⑤中原町 | ⑥294 | ⑦294 | ⑧井野台 | | | 合計 | | | | | | | |
| 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | + | 3.000 | + | 0.000 | + | 0.000 | + | 0.000 | = | 3.0 | m |
| 設計値 | | | | | | | | | | | | | | = | 3 | m | |

6国補第66-116号舗装復旧工事

補助

舗装切断工

| | | | | | | | | | | |
|---------------------------|------|---------|------|--------|---|--------|-----|--------|----------------|----------------|
| ⑨白山 | ⑩中原町 | ⑪中原町 | ⑫294 | 合計 | | | | | | |
| 0.00 | + | 8.80 | + | 5.30 | + | 0.00 | = | 14.10 | m | |
| | | | | | | | 設計値 | = | 14 | m |
| 舗装版掘削積込(As) | | | | | | | | | | |
| ⑨白山 | ⑩中原町 | ⑪中原町 | ⑫294 | 合計 | | | | | | |
| 328.596 | + | 106.353 | + | 68.751 | + | 75.652 | = | 579.35 | m ² | |
| | | | | | | | 設計値 | = | 579 | m ² |
| 不陸整正3.1未満(補足有) | | | | | | | | | | |
| ⑨白山 | ⑩中原町 | ⑪中原町 | ⑫294 | 合計 | | | | | | |
| 167.943 | + | 0.000 | + | 68.751 | + | 0.000 | = | 236.7 | m ² | |
| | | | | | | | 設計値 | = | 236 | m ² |
| 不陸整正3.1以上(補足有) | | | | | | | | | | |
| ⑨白山 | ⑩中原町 | ⑪中原町 | ⑫294 | 合計 | | | | | | |
| 160.653 | + | 106.353 | + | 0.000 | + | 75.652 | = | 342.7 | m ² | |
| | | | | | | | 設計値 | = | 342 | m ² |
| 舗装工(再密As) 車道3.0超 | | | | | | | | | | |
| ⑨白山 | ⑩中原町 | ⑪中原町 | ⑫294 | 合計 | | | | | | |
| 208.051 | + | 106.353 | + | 0.000 | + | 75.652 | = | 390.1 | m ² | |
| | | | | | | | 設計値 | = | 390 | m ² |
| 舗装工(再密As) 車道1.4～3.0 | | | | | | | | | | |
| ⑨白山 | ⑩中原町 | ⑪中原町 | ⑫294 | 合計 | | | | | | |
| 120.545 | + | 0.000 | + | 68.751 | + | 0.000 | = | 189.3 | m ² | |
| | | | | | | | 設計値 | = | 189 | m ² |
| 殻運搬処理(As t ≤ 15cm) | | | | | | | | | | |
| ⑨白山 | ⑩中原町 | ⑪中原町 | ⑫294 | 合計 | | | | | | |
| 16.430 | + | 5.318 | + | 3.438 | + | 3.783 | = | 29.0 | m ³ | |
| | | | | | | | 設計値 | = | 28 | m ³ |
| 区画線設置(実線15cm) 外側線 | | | | | | | | | | |
| ⑨白山 | ⑩中原町 | ⑪中原町 | ⑫294 | 合計 | | | | | | |
| 0.000 | + | 0.000 | + | 0.000 | + | 0.000 | = | 0.0 | m | |
| | | | | | | | 設計値 | = | 0 | m |
| 区画線設置(矢印・記号・文字) ダイヤ・止まれ | | | | | | | | | | |
| ⑨白山 | ⑩中原町 | ⑪中原町 | ⑫294 | 合計 | | | | | | |
| 0.000 | + | 0.000 | + | 0.000 | + | 13.400 | = | 13.4 | m | |
| | | | | | | | 設計値 | = | 13 | m |
| 区画線設置(実線線45cm) 横断歩道 + 停止線 | | | | | | | | | | |
| ⑨白山 | ⑩中原町 | ⑪中原町 | ⑫294 | 合計 | | | | | | |
| 0.000 | + | 0.000 | + | 0.000 | + | 1.600 | = | 1.6 | m | |
| | | | | | | | 設計値 | = | 1 | m |

白山4丁目 (BP1) 単独

| 測点(No.) | 幅員(m) | 平均(m) | 延長(m) | 控除(m ²) | 面積(m ²) |
|-----------|--------|--------|---------|----------------------|-----------------------|
| BP1 | 2.900m | | | | |
| | | 3.100m | 6.000m | | 18.600m ² |
| BP1+6.00 | 3.300m | | | | |
| BP1+6.00 | 3.650m | | | | |
| | | 3.625m | 8.500m | | 30.813m ² |
| BP1+14.50 | 3.600m | | | | |
| BP1+14.50 | 3.500m | | | | |
| | | 3.450m | 5.500m | | 18.975m ² |
| No1 | 3.400m | | | | |
| | | 3.450m | 20.000m | | 69.000m ² |
| No2 | 3.500m | | | | |
| | | 3.500m | 12.800m | | 44.800m ² |
| No2+12.80 | 3.500m | | | | |
| No2+12.80 | 4.100m | | | | |
| | | 4.075m | 5.500m | | 22.413m ² |
| No2+18.30 | 4.050m | | | | |
| No2+18.30 | 3.400m | | | | |
| | | 3.400m | 1.700m | | 5.780m ² |
| No3 | 3.400m | | | | |
| | | 3.425m | 11.000m | | 37.675m ² |
| No3+11.00 | 3.450m | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| 合計面積 | | | | 71.102m ² | 176.954m ² |

白山4丁目 (BP1) 単独

舗装版切断工 2.90m + + = 2.900m
+ + + =

不陸整正 (3.1未満補足材あり) =
不陸整正 (3.1以上補足材あり) = 176.954m²
表層工 1.4~3.0m =
表層工 3.0m超 = 176.954m²

舗装塊 As塊 176.954m² × 0.05m = 8.848m³

区画線45 横断歩道 =
停止線 =
区画線20 ダイヤ =
区画線15 消火栓 =

| 白山4丁目（BP2～BP5） 単独 | | | | | |
|-------------------|---------------------|--------|---------|---------------------|-----------------------|
| 測点(No.) | 幅員(m) | 平均(m) | 延長(m) | 控除(m ²) | 面積(m ²) |
| BP2 | 4.300m | | | | |
| BP2+17.70 | 4.100m | 4.200m | 17.700m | 1.482m ² | 72.858m ² |
| BP3 | 5.500m | | | | |
| BP3+2.00 | 3.800m | 4.650m | 2.000m | | 9.300m ² |
| BP3+4.20 | 3.400m | 3.600m | 2.200m | 0.384m ² | 7.536m ² |
| No1 | 3.500m | 3.450m | 15.800m | | 54.510m ² |
| No1+1.20 | 4.300m | 3.900m | 1.200m | | 4.680m ² |
| BP4 | 3.200m | | | | |
| No1 | 3.150m | 3.175m | 20.000m | 0.948m ² | 62.552m ² |
| No2 | 3.100m | 3.125m | 20.000m | 0.282m ² | 62.218m ² |
| No2+5.30 | 3.000m | 3.050m | 5.300m | 0.282m ² | 15.883m ² |
| BP5 | 3.000m | | | | |
| BP5+12.95 | 3.800m | 3.400m | 12.950m | 0.831m ² | 43.199m ² |
| BP5+12.95 | 3.400m | | | | |
| BP5+17.20 | 3.700m | 3.550m | 4.250m | | 15.088m ² |
| BP5+18.30 | 4.100m | 3.900m | 1.100m | | 4.290m ² |
| BP5+20.45 | 5.800m | 4.950m | 2.150m | 0.038m ² | 10.605m ² |
| BP5+20.45 | 7.100m | | | | |
| BP5+21.30 | 7.100m | 7.100m | 0.850m | | 6.035m ² |
| BP6 | 3.300m | | | | |
| BP6+12.10 | 3.300m | 3.300m | 12.100m | 1.128m ² | 38.802m ² |
| | | | | | |
| | a | b | c | | |
| 三角形① | 2.900m | 3.300m | 1.600m | | 2.319m ² |
| | s=1/2(a+b+c) | | = 3.900 | | |
| | S=√s(s-a)(s-b)(s-c) | | = 2.320 | | |
| | a | b | c | | |
| 三角形② | 3.300m | 3.100m | 1.200m | 0.360m ² | 1.859m ² |
| | s=1/2(a+b+c) | | = 3.800 | | |
| | S=√s(s-a)(s-b)(s-c) | | = 1.860 | | |
| | a | b | c | | |
| 三角形③ | 1.500m | 1.500m | 1.500m | | 0.974m ² |
| | s=1/2(a+b+c) | | = 2.250 | | |
| | S=√s(s-a)(s-b)(s-c) | | = 0.974 | | |
| 台形① | 3.100m | 2.500m | 5.750m | 0.402m ² | 16.100m ² |
| | | | | | |
| 合計面積 | | | | 6.137m ² | 422.671m ² |

白山4丁目（BP2～BP5） 単独

| | | | | | | | |
|------------------|-------|-----------------------|-------|-------|-------|---|-----------------------|
| 舗装版切断工 | 4.30m | + | 3.30m | + | 3.00m | = | 10.600m |
| | | + | | + | | | |
| 不陸整正（3.1未満補足材あり） | | | | | | = | 15.883m ² |
| 不陸整正（3.1以上補足材あり） | | | | | | = | 406.788m ² |
| 表層工 1.4～3.0m | | | | | | = | |
| 表層工 3.0m超 | | | | | | = | 422.671m ² |
| 舗装塊 | As塊 | 422.671m ² | × | 0.05m | | = | 21.134m ³ |
| 区画線45 | 横断歩道 | | | | | = | |
| | 停止線 | | | | | = | |
| 区画線20 | ダイヤ | | | | | = | |
| 区画線15 | 消火栓 | | | | | = | |

白山4丁目（BP7～BP8） 単独

| 測点(No.) | 幅員(m) | 平均(m) | 延長(m) | 控除(m ²) | 面積(m ²) |
|-----------|--------|--------|---------|---------------------|-----------------------|
| BP7 | 2.800m | | | | |
| | | 2.650m | 3.100m | 0.025m ² | 8.190m ² |
| BP7+3.10 | 2.500m | | | | |
| BP7+3.10 | 3.200m | | | | |
| | | 3.000m | 16.900m | | 50.700m ² |
| No1 | 2.800m | | | | |
| | | 2.400m | 20.700m | 0.050m ² | 49.630m ² |
| No1+20.70 | 2.000m | | | | |
| BP8 | 3.300m | | | | |
| | | 3.100m | 10.400m | | 32.240m ² |
| BP8+10.40 | 2.900m | | | | |
| | | | | | |
| BP8+10.40 | 2.600m | | | | |
| | | 2.350m | 2.900m | | 6.815m ² |
| BP8+13.30 | 2.100m | | | | |
| | | | | | |
| BP8+13.30 | 2.400m | | | | |
| | | 2.400m | 6.000m | | 14.400m ² |
| BP8+19.30 | 2.400m | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| 合計面積 | | | | 0.075m ² | 161.900m ² |

白山4丁目（BP7～BP8） 単独

舗装版切断工 0.00m + + = 0.000m
+ + + =

不陸整正（3.1未満補足材あり） = 129.660m²
不陸整正（3.1以上補足材あり） = 32.240m²
表層工 1.4～3.0m = 78.960m²
表層工 3.0m超 = 82.940m²

舗装塊 As塊 161.900m² × 0.05m = 8.095m³

区画線45 横断歩道 =
停止線 =
区画線20 ダイヤ =
区画線15 消火栓 =

中原町 (BP1) 単独

| 測点 (No.) | 幅員 (m) | 平均 (m) | 延長 (m) | 控除 (m ²) | 面積 (m ²) |
|-----------|-----------------------------|--------|---------|----------------------|----------------------|
| BP1 | 3.600m | 3.850m | 17.700m | | 68.145m ² |
| BP1+17.70 | 4.100m | | | | |
| | a | b | c | | |
| 三角形① | 4.100m | 3.300m | 5.000m | | 6.731m ² |
| | $s=1/2(a+b+c)$ | | = 6.200 | | |
| | $S=\sqrt{s(s-a)(s-b)(s-c)}$ | | = 6.731 | | |
| | | | | | |
| 合計面積 | | | | 2.695m ² | 72.181m ² |

中原町 (BP1) 単独

舗装版切断工 3.60m + + = 3.600m
 + + + =

不陸整正 (3.1未満補足材あり) =
 不陸整正 (3.1以上補足材あり) = 72.181m²
 表層工 1.4~3.0m =
 表層工 3.0m超 = 72.181m²

舗装塊 As塊 72.181m² × 0.05m = 3.609m³

区画線45 横断歩道 =
 停止線 =
 区画線20 ダイヤ =
 区画線15 消火栓 =

中原町 (BP2～BP3) 単独

| 測点 (No.) | 幅員 (m) | 平均 (m) | 延長 (m) | 控除 (m ²) | 面積 (m ²) |
|-----------|--------|--------|---------|----------------------|-----------------------|
| BP2 | 3.950m | | | | |
| | | 3.950m | 13.500m | 0.905m ² | 52.420m ² |
| BP2+13.50 | 3.950m | | | | |
| BP2+13.50 | 3.000m | | | | |
| | | 3.175m | 6.500m | | 20.638m ² |
| No1 | 3.350m | | | | |
| | | 3.350m | 0.600m | | 2.010m ² |
| No1+0.60 | 3.350m | | | | |
| No1+0.60 | 3.600m | | | | |
| | | 3.625m | 4.100m | | 14.863m ² |
| No1+4.70 | 3.650m | | | | |
| No1+4.70 | 4.000m | | | | |
| | | 3.975m | 11.000m | 1.338m ² | 42.387m ² |
| No1+15.70 | 3.950m | | | | |
| | | 3.500m | 4.300m | | 15.050m ² |
| No2 | 3.050m | | | | |
| | | 3.025m | 5.950m | | 17.999m ² |
| No2+5.95 | 3.000m | | | | |
| No2+5.95 | 3.950m | | | | |
| | | 3.950m | 3.150m | | 12.443m ² |
| No2+9.10 | 3.950m | | | | |
| No2+9.10 | 3.050m | | | | |
| | | 3.050m | 10.900m | 0.049m ² | 33.196m ² |
| No3 | 3.050m | | | | |
| | | 3.175m | 5.700m | 0.988m ² | 17.110m ² |
| No3+5.70 | 3.300m | | | | |
| BP3 | 3.700m | | | | |
| | | 3.250m | 20.000m | | 65.000m ² |
| No1 | 2.800m | | | | |
| | | 2.950m | 5.200m | | 15.340m ² |
| No1+5.20 | 3.100m | | | | |
| No1+5.20 | 2.400m | | | | |
| | | 3.100m | 3.500m | 0.307m ² | 10.543m ² |
| No1+8.70 | 3.800m | | | | |
| | | | | | |
| | | | | | |
| 合計面積 | | | | 3.587m ² | 315.412m ² |

中原町 (BP2～BP3) 単独

$$\begin{array}{rcllcll} \text{舗装版切断工} & 3.95\text{m} & + & 3.80\text{m} & + & & \\ & + & & + & + & = & 7.750\text{m} \end{array}$$

$$\begin{array}{rcll} \text{不陸整正 (3.1未満補足材あり)} & = & 66.535\text{m}^2 \\ \text{不陸整正 (3.1以上補足材あり)} & = & 248.877\text{m}^2 \\ \text{表層工 1.4～3.0m} & = & 15.340\text{m}^2 \\ \text{表層工 3.0m超} & = & 300.072\text{m}^2 \end{array}$$

$$\begin{array}{rcllcll} \text{舗装塊} & \text{As塊} & 315.412\text{m}^2 & \times & 0.05\text{m} & = & 15.771\text{m}^3 \end{array}$$

$$\begin{array}{rcll} \text{区画線45 横断歩道} & = & & \\ \text{停止線} & = & & \\ \text{区画線20 ダイヤ} & = & & \\ \text{区画線15 消火栓} & = & & \end{array}$$

白山4丁目294（BP1～BP2） 単独

| 測点 (No.) | 幅員 (m) | 平均 (m) | 延長 (m) | 控除 (m ²) | 面積 (m ²) |
|------------|-----------------------------------|----------|----------|----------------------|----------------------|
| BP1 | 2. 600m | 2. 600m | 7. 400m | | 19. 240m2 |
| BP1+7. 40 | 2. 600m | | | | |
| BP1+7. 40 | 5. 600m | 5. 275m | 12. 600m | 2. 250m2 | 64. 215m2 |
| No1 | 4. 950m | | | | |
| No2 | 3. 600m | 4. 275m | 20. 000m | 0. 564m2 | 84. 936m2 |
| | | 3. 625m | 26. 650m | 0. 358m2 | 96. 248m2 |
| No2+26. 65 | 3. 650m | | | | |
| BP2 | 3. 500m | 3. 600m | 4. 100m | 1. 609m2 | 13. 151m2 |
| BP2+4. 10 | 3. 700m | | | | |
| BP2+4. 10 | 3. 400m | 3. 250m | 15. 900m | 0. 101m2 | 51. 574m2 |
| No1 | 3. 100m | | | | |
| No2 | 3. 700m | 3. 400m | 20. 000m | 1. 334m2 | 66. 666m2 |
| | | 3. 775m | 8. 500m | | |
| No2+8. 50 | 3. 850m | | | | |
| | | | | | |
| | | | | | |
| | a | b | c | | |
| 三角形① | 16. 500m | 16. 500m | 2. 150m | 0. 180m2 | 17. 699m2 |
| | s=1/2 (a+b+c) = 17. 575 | | | | |
| | S=√ s (s-a) (s-b) (s-c) = 17. 700 | | | | |
| | | | | | |
| | | | | | |
| 合計面積 | | | | 6. 396m2 | 407. 333m2 |

白山4丁目294（BP1～BP2） 単独

舗装版切断工

2.60m

+

2.15m

+

3.50m

+

4.10m

+

3.85m

+

=

16.200m

不陸整正（3.1未満補足材あり）

=

36.939m²

不陸整正（3.1以上補足材あり）

=

370.394m²

表層工 1.4～3.0m

=

36.939m²

表層工 3.0m超

=

370.394m²

舗装塊

As塊

407.333m²

×

0.05m

=

20.367m³

止まれ 4m未満

1箇所

=

13.4m

区画線45 破線

=

3.0m

停止線

=

2.0m

区画線20 ダイヤ

=

区画線15 消火栓

=

外側線

=

47.0m

白山4丁目294 (BP3) 単独

| 測点(No.) | 幅員(m) | 平均(m) | 延長(m) | 控除(m ²) | 面積(m ²) |
|-----------|-------------------------|--------|---------|---------------------|----------------------|
| BP3 | 3.700m | 3.475m | 16.800m | | 58.380m ² |
| BP3+16.80 | 3.250m | | | | |
| | a | b | c | | |
| 三角形① | 3.250m | 5.200m | 3.000m | | 4.502m ² |
| | s=1/2 (a+b+c) | | = 5.725 | | |
| | S=√ s (s-a) (s-b) (s-c) | | = 4.502 | | |
| | | | | | |
| 合計面積 | | | | 0.114m ² | 62.768m ² |

白山4丁目294 (BP3) 単独

舗装版切断工 5.20m + + = 5.200m
 + + + =

不陸整正 (3.1未満補足材あり) =
 不陸整正 (3.1以上補足材あり) = 62.768m²
 表層工 1.4~3.0m =
 表層工 3.0m超 = 62.768m²

舗装塊 As塊 62.768m² × 0.05m = 3.138m³

止まれ 1箇所 = 13.4m
 区画線45 横断歩道 =
 停止線 = 1.6m
 区画線20 ダイヤ =
 区画線15 消火栓 =

井野台3丁目 单独

| 測点(No.) | 幅員(m) | 平均(m) | 延長(m) | 控除(m ²) | 面積(m ²) |
|---------|--------|--------|--------|---------------------|----------------------|
| | | | | | |
| 台形① | 1.700m | 4.600m | 4.800m | | 15.120m ² |
| | | | | | |
| 合計面積 | | | | | 15.120m ² |

井野台3丁目 单独

| | | | | | |
|--------|--------|---|---|---|---------|
| 鋪裝版切斷工 | 10.00m | + | + | | |
| | + | + | + | = | 10.000m |

| | | |
|-------------------|---|----------------------|
| 不陸整正 (3.1未満補足材あり) | = | |
| 不陸整正 (3.1以上補足材あり) | = | 15.120m ² |
| 表層工 1.4～3.0m | = | |
| 表層工 3.0m超 | = | 15.120m ² |

$$\text{鋪裝塊 As塊 } 15.120\text{m}^2 \times 0.05\text{m} = 0.756\text{m}^3$$

| | | |
|-------|------|---|
| 区画線45 | 横断歩道 | = |
| | 停止線 | = |
| 区画線20 | ダイヤ | = |
| 区画線15 | 消火栓 | = |

白山4丁目 (BP1～BP2) 補助

| 測点 (No.) | 幅員 (m) | 平均 (m) | 延長 (m) | 控除 (m ²) | 面積 (m ²) |
|-----------|--------|--------|---------|----------------------|-----------------------|
| BP1 | 2.900m | | | | |
| No1 | 2.750m | 2.825m | 20.000m | 0.564m ² | 55.936m ² |
| No1+4.30 | 2.500m | 2.625m | 4.300m | 0.282m ² | 11.006m ² |
| No1+4.30 | 4.000m | | | | |
| No1+9.70 | 3.600m | 3.800m | 5.400m | | 20.520m ² |
| No1+9.70 | 3.000m | | | | |
| No2 | 3.200m | 3.100m | 10.300m | | 31.930m ² |
| No2+16.00 | 2.800m | 3.000m | 16.000m | 0.602m ² | 47.398m ² |
| BP2 | 4.350m | | | | |
| BP2+17.80 | 2.750m | 3.550m | 17.800m | | 63.190m ² |
| BP2+17.80 | 4.000m | | | | |
| No1 | 3.800m | 3.900m | 2.200m | | 8.580m ² |
| No1+10.30 | 3.900m | 3.850m | 10.300m | | 39.655m ² |
| No1+10.30 | 2.600m | | | | |
| No2 | 2.350m | 2.475m | 9.700m | 0.990m ² | 23.018m ² |
| No2+11.95 | 2.900m | 2.625m | 11.950m | 0.784m ² | 30.585m ² |
| | | | | | |
| | | | | | |
| 合計面積 | | | | 3.222m ² | 328.596m ² |

白山4丁目 (BP1～BP2) 補助

舗装版切断工 + + + = 0.000m

不陸整正 (3.1未満補足材あり) = 167.943m²

不陸整正 (3.1以上補足材あり) = 160.653m²

表層工 1.4～3.0m = 120.545m²

表層工 3.0m超 = 208.051m²

舗装塊 As塊 328.596m² × 0.05m = 16.430m³

区画線45 横断歩道 =

停止線 =

区画線20 ダイヤ =

区画線15 消火栓 =

中原町(BP1～BP2) 補助

| 測点(No.) | 幅員(m) | | | 平均(m) | 延長(m) | 控除(m ²) | 面積(m ²) |
|-----------|--------|--|--|--------|---------|---------------------|-----------------------|
| BP1 | 5.400m | | | 4.225m | 3.300m | | 13.943m ² |
| BP1+3.30 | 3.050m | | | | | | |
| BP1+16.75 | 3.250m | | | 3.150m | 13.450m | | |
| BP2 | 5.400m | | | 4.325m | 2.100m | | 9.083m ² |
| BP2+2.10 | 3.250m | | | | | | |
| BP2+28.00 | 3.400m | | | 3.325m | 25.900m | | 86.118m ² |
| | | | | | | | |
| | | | | | | | |
| 合計面積 | | | | | | 2.791m ² | 106.353m ² |

中原町(BP1~BP2) 補助

$$\begin{array}{rclclcl} \text{鋪裝版切断工} & 5.40\text{m} & + & 3.40\text{m} & + & \\ & + & & & + & = 8.800\text{m} \end{array}$$

| | | |
|-------------------|---|-----------------------|
| 不陸整正 (3.1未満補足材あり) | = | |
| 不陸整正 (3.1以上補足材あり) | = | 106.353m ² |
| 表層工 1.4～3.0m | = | |
| 表層工 3.0m超 | = | 106.353m ² |

$$\text{舖装塊 As塊 } 106.353\text{m}^2 \times 0.05\text{m} = 5.318\text{m}^3$$

| | | |
|-------|------|---|
| 区画線45 | 横断歩道 | = |
| | 停止線 | = |
| 区画線20 | ダイヤ | = |
| 区画線15 | 消火栓 | = |

中原町(BP3) 補助

| 測点(No.) | 幅員(m) | 平均(m) | 延長(m) | 控除(m ²) | 面積(m ²) |
|-----------|---------------------|--------|---------|---------------------|----------------------|
| BP3 | 2.600m | 2.525m | 27.800m | | 70.195m ² |
| BP3+27.80 | 2.450m | | | | |
| | | | | | |
| | a | b | c | | |
| 三角形① | 2.450m | 2.700m | 1.100m | | 1.347m ² |
| | s=1/2(a+b+c) | | = 3.125 | | |
| | S=√s(s-a)(s-b)(s-c) | | = 1.347 | | |
| | | | | | |
| | | | | | |
| 合計面積 | | | | 2.791m ² | 68.751m ² |

中原町(BP3) 補助

$$\begin{array}{rclclcl} \text{舗装版切断工} & 2.60\text{m} & + & 2.70\text{m} & + & \\ & + & & + & + & = 5.300\text{m} \end{array}$$

$$\begin{array}{rcl} \text{不陸整正 (3.1未満補足材あり)} & & = 68.751\text{m}^2 \end{array}$$

$$\begin{array}{rcl} \text{不陸整正 (3.1以上補足材あり)} & & = \end{array}$$

$$\begin{array}{rcl} \text{表層工 1.4} \sim 3.0\text{m} & & = 68.751\text{m}^2 \end{array}$$

$$\begin{array}{rcl} \text{表層工 3.0m超} & & = \end{array}$$

$$\begin{array}{rclclcl} \text{舗装塊} & \text{As塊} & 68.751\text{m}^2 & \times & 0.05\text{m} & = 3.438\text{m}^3 \end{array}$$

$$\begin{array}{rcl} \text{区画線45 横断歩道} & & = \end{array}$$

$$\begin{array}{rcl} \text{停止線} & & = \end{array}$$

$$\begin{array}{rcl} \text{区画線20 ダイヤ} & & = \end{array}$$

$$\begin{array}{rcl} \text{区画線15 消火栓} & & = \end{array}$$

白山4丁目294(BP1) 補助

| 測点(No.) | 幅員(m) | 平均(m) | 延長(m) | 控除(m ²) | 面積(m ²) |
|-----------|-------------------------------------|--------|---------|---------------------|----------------------|
| BP1 | 3.550m | 3.375m | 14.200m | | 47.925m ² |
| BP1+14.20 | 3.200m | | | | |
| BP1+14.20 | 3.600m | 3.650m | 3.800m | | 13.870m ² |
| BP1+18.00 | 3.700m | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | a | b | c | | |
| 三角形① | 5.100m | 6.250m | 3.550m | | 9.051m ² |
| | $s=1/2(a+b+c) = 7.450$ | | | | |
| | $S=\sqrt{s(s-a)(s-b)(s-c)} = 9.052$ | | | | |
| | a | b | c | | |
| 三角形② | 6.250m | 7.000m | 1.800m | | 5.370m ² |
| | $s=1/2(a+b+c) = 7.525$ | | | | |
| | $S=\sqrt{s(s-a)(s-b)(s-c)} = 5.370$ | | | | |
| | | | | | |
| 合計面積 | | | | 0.564m ² | 75.652m ² |

白山4丁目294(BP1) 補助

| | | | | | | |
|-------------------|------|----------|---|-------|---|------------|
| 舗装版切断工 | | + | | + | | |
| | + | | + | | + | = 0.000m |
| 不陸整正 (3.1未満補足材あり) | | | | | | = |
| 不陸整正 (3.1以上補足材あり) | | | | | | = 75.652m2 |
| 表層工 1.4～3.0m | | | | | | = |
| 表層工 3.0m超 | | | | | | = 75.652m2 |
| 舗装塊 | As塊 | 75.652m2 | × | 0.05m | | = 3.783m3 |
| 止まれ | | | | 1箇所 | | = 13.4m |
| 区画線45 | 横断歩道 | | | | | = |
| | 停止線 | | | | | = 1.6m |
| 区画線20 | ダイヤ | | | | | = |
| 区画線15 | 消火栓 | | | | | = |